

1. GENERAL

- A. PLAN THE SEQUENCE OF CONSTRUCTION SO THAT THE SMALLEST PRACTICAL AREA OF LAND IS EXPOSED AT ANY ONE TIME DURING CONSTRUCTION. SCHEDULE THE WORK SUCH THAT SEDIMENTATION BARRIERS AND DETENTION PONDS ARE INSTALLED EARLY IN THE CONSTRUCTION SEQUENCE. TO PREVENT SEDIMENTS FROM UPHILL AREAS REACHING STREAMS, WETLANDS OR PROPERTY LINES. THE AREA DISTURBED BY STRIPPING OF VEGETATION, SOIL REMOVAL, AND REGARDING SHALL BE THE MINIMUM NECESSARY AT ANY ONE TIME. THE DURATION OF EXPOSURE OF THE DISTURBED AREA SHALL BE KEPT TO A PRACTICAL MINIMUM. UNTIL A DISTURBED AREA IS STABILIZED, SEDIMENT IN RUN-OFF SHALL BE TRAPPED BY THE USE OF DEBRIS BASIN, SEDIMENT BASINS, SILT TRAPS OR OTHER ACCEPTABLE METHODS.
- C. TAKE NECESSARY STEPS TO PREVENT SOIL EROSION. REFER TO PUBLICATION OF MAINE DEP PARTICULARLY CHAPTER 500, AND THE MAINE SOIL AND WATER CONSERVATION COMMISSION FOR ADDITIONAL PREVENTION MEASURES TO STOP SOIL EROSION AND FOLLOW DEP MAINE EROSION AND SEDIMENT CONTROL BMP'S. THE CONTRACTOR SHALL CONDUCT HIS OPERATIONS IN CONFORMITY WITH ALL FEDERAL AND STATE PERMIT REQUIREMENTS CONCERNING WATER, AIR OR NOISE POLLUTION, OR THE DISPOSAL OF CONTAMINATED OR HAZARDOUS MATERIALS. EROSION CONTROL MEASURES SHOWN ON THE PLANS ARE MINIMUM ONLY. SATISFY THE CURRENT REQUIREMENTS OF THE REGULATORY AGENCIES. REPAIR ALL AREAS OF INSTABILITY AND EROSION IMMEDIATELY AND MAINTAIN UNTIL THE SITE IS FULLY STABILIZED.
- E. WHENEVER PRACTICABLE, NO DISTURBANCE ACTIVITIES SHOULD TAKE PLACE WITHIN 50 FEET OF ANY PROTECTED NATURAL RESOURCE. IF DISTURBANCE ACTIVITIES TAKE PLACE BETWEEN 30 FEET AND 50 FEET OF ANY PROTECTED NATURAL RESOURCE, AND STORMWATER DISCHARGES THROUGH THE DISTURBED AREAS TOWARD THE PROTECTED NATURAL RESOURCE, PERIMETER EROSION CONTROLS MUST BE DOUBLED. IF DISTURBANCE ACTIVITIES TAKE PLACE LESS THAN 30 FEET FROM ANY PROTECTED NATURAL RESOURCE, AND STORMWATER DISCHARGES THROUGH THE DISTURBED AREAS TOWARD THE PROTECTED NATURAL RESOURCE, PERIMETER EROSION CONTROLS MUST BE DOUBLED AND DISTURBED AREAS MUST BE TEMPORARILY OR PERMANENTLY STABILIZED WITH 7 DAYS.
- H. SILT FENCE:
POST: 1"X1" HARDWOOD POST, 4.5 FEET IN LENGTH.
FABRIC: PERVIOUS 36" WIDE SHEET OF SYNTHETIC POLYMER OF 12-MIL THICKNESS, SUCH AS MIRAFI 100X; TERRA TEX-SC OR APPROVED EQUAL. THE BOTTOM OF THE FABRIC SHALL BE TRENCHED INTO THE EXISTING GROUND A MINIMUM OF 6 INCHES. IN ADDITION, HAY BALES OR DITCH CHECKS SHALL BE INSTALLED ALONG THE SILT FENCE TO CREATE SEDIMENTATION POOLS IN LOW AREAS WHERE RUN-OFF CONCENTRATES.
- J. HAY BALES: BALES SHALL BE AT LEAST 14" X 18" X 30" IN SIZE, STAKED TWICE PER BALE. STAKES SHALL BE 1" X 1" X 36" WOODEN. PLACE BALES WITH TWINE ON SIDES OF BALE, NOT TOP OR BOTTOM.
- K. CATCH BASIN SEDIMENT FILTER SACK: A FILTER FABRIC BAG WHICH HANGS UNDER THE GRATE TO CATCH SEDIMENTS. PROVIDE "STREAMGUARD MODEL 3003," "BASIN BAG" BY EMCO DISTRIBUTION, "SILT SACKS HIGH FLOW" BY ACF ENVIRONMENTAL, OR APPROVED EQUAL. INSTALL THE BAG DEVICE PER MANUFACTURER'S RECOMMENDATION.
- L. BEFORE EARTHWORK IS STARTED, A SILT FENCE, FILTER BERM, OR STONE SEDIMENT DAM SHALL BE INSTALLED ALONG THE DOWN-SLOPE SIDE OF THE CONSTRUCTION SITE, AS NECESSARY, TO PREVENT SOIL SEDIMENT MIGRATION AWAY FROM THE SITE. INSTALL SILT FENCE OR FILTER BERM ALONG THE DOWN-SLOPE SIDE OF ALL TOP-SOIL AND SUBSOIL STOCKPILES.
- M. EROSION CONTROLS BARRIERS SHALL BE REMOVED AFTER CONSTRUCTION IS COMPLETE, BUT NOT UNTIL FINISH GRADING, FINAL SEEDING, AND MULCHING HAS BEEN COMPLETED AND THE ESTABLISHED GRASS HAS STABILIZED THE SOIL. MAINTAIN BARRIERS IN GOOD CONDITION UNTIL REMOVED.
- N. INSPECT EROSION AND SEDIMENTATION CONTROL WEEKLY AND AFTER STORM AND MAINTAIN IN GOOD WORKING CONDITION FOR PROJECT DURATION. REMOVE SILT DEPOSITS FROM THE SITE, PLACE IN AN AREA OF LOW EROSION POTENTIAL SO IT WILL NOT WASH INTO A WETLAND OR WATER BODY, SEED WITH EROSION CONTROL MIX, AND MULCH.
- P. TEMPORARY STABILIZATION: WITHIN 7 DAYS OF THE CESSATION OF CONSTRUCTION ACTIVITIES IN AN AREA THAT WILL NOT BE WORKED FOR MORE THAN 7 DAYS, STABILIZE EXPOSED SOIL WITH MULCH, OR OTHER NON-ERODIBLE COVER. STABILIZE AREAS WITHIN 75 FEET OF A WETLAND OR WATERBODY WITHIN 48 HOURS OF THE INITIAL DISTURBANCE OF THE SOIL OR PRIOR TO A STORM EVENT, WHICHEVER COMES FIRST. REMOVE TEMPORARY CONTROL MEASURES, SUCH AS SILT FENCE, WITHIN 30 DAYS AFTER PERMANENT STABILIZATION IS ATTAINED. REMOVE ANY ACCUMULATED SEDIMENTS AND STABILIZE. MAINTAIN TEMPORARY EROSION CONTROL MEASURES FOR THE FULL DURATION OF CONSTRUCTION. INSPECT WEEKLY AND AFTER EACH STORM AND REPAIR AS NEEDED. REMOVE SEDIMENTS FROM THE SITE, PLACE IN AREA OF LOW EROSION POTENTIAL, AND STABILIZE WITH SEED AND MULCH.
- Q. PERMANENT STABILIZATION: IF THE AREA WILL NOT BE WORKED FOR MORE THAN ONE YEAR OR HAS BEEN BROUGHT TO FINAL GRADE, THEN PERMANENTLY STABILIZE THE AREA WITHIN 7 DAYS BY PLANTING VEGETATION, SEEDING, SOOD, OR THROUGH THE USE OF PERMANENT MULCH, OR RIPRAP, OR ROAD SUB-BASE. IF USING VEGETATION FOR STABILIZATION, SELECT THE PROPER VEGETATION FOR THE LIGHT, MOISTURE, AND SOIL CONDITIONS. AMEND AREAS OF DISTURBED SUBSOILS WITH TOPSOIL, COMPOST, OR FERTILIZERS; PROTECT SEEDED AREAS WITH MULCH OR, IF NECESSARY, EROSION CONTROL BLANKETS; AND SCHEDULE SOODING, PLANTING, AND SEEDING SO TO AVOID DIE-OFF FROM SUMMER DROUGHT AND FALL FROSTS. NEWLY SEEDDED OR SOODDED AREAS MUST BE PROTECTED FROM VEHICLE TRAFFIC, EXCESSIVE PEDESTRIAN TRAFFIC, AND CONCENTRATED RUNOFF UNTIL VEGETATION IS WELL-ESTABLISHED WITH 90% COVER BY HEALTHY VEGETATION. IF NECESSARY, AREAS MUST BE REWORKED AND RESTABILIZED IF GERMINATION IS SPARSE, PLANT COVERAGE IS SPOTTY, OR TOPSOIL EROSION IS EVIDENT. PERMANENT STABILIZATION IS DEFINED AS FOLLOWS:

1. SEEDDED AREAS: PERMANENT STABILIZATION MEANS A 90% COVER OF THE DISTURBED AREA WITH MATURE, HEALTHY PLANTS WITH NO EVIDENCE OF WASHING OR RILLING OF THE TOPSOIL.
2. SOODDED AREAS: PERMANENT STABILIZATION MEANS THE COMPLETE BINDING OF THE SOOD ROOTS INTO THE UNDERLYING SOIL WITH NO SLUMPING OF THE SOOD OR DIE-OFF.
3. PERMANENT MULCH: PERMANENT MULCHING MEANS TOTAL COVERAGE OF THE EXPOSED AREA WITH AN APPROVED MULCH MATERIAL. EROSION CONTROL MIX MAY BE USED AS MULCH FOR PERMANENT STABILIZATION ACCORDING TO THE APPROVED APPLICATION RATES AND LIMITATIONS.
4. RIPRAP: PERMANENT STABILIZATION MEANS THAT SLOPES STABILIZED WITH RIPRAP HAVE AN APPROPRIATE BACKING OF A WELL-GRADED GRAVEL OR APPROVED GEOTEXTILE TO PREVENT SOIL MOVEMENT FROM BEHIND THE RIPRAP. STONE MUST BE SIZED APPROPRIATELY. IT IS RECOMMENDED THAT ANGULAR STONE BE USED.
5. PAVED AREAS: PERMANENT STABILIZATION MEANS PLACEMENT OF THE COMPACTED GRAVEL SUBBASE IS COMPLETED, PROVIDED IT IS FREE OF FINE MATERIALS THAT MAY RUNOFF WITH A RAIN EVENT.
6. DITCHES, CHANNELS, AND SWALES: PERMANENT STABILIZATION MEANS THE CHANNEL IS STABILIZED WITH A 90% COVER OF HEALTHY VEGETATION, WITH A WELL-GRADED RIPRAP LINING, TURF REINFORCEMENT MAT, OR WITH ANOTHER NON-EMISIVE LINING SUCH AS CONCRETE OR ASPHALT PAVEMENT. THERE MUST BE NO EVIDENCE OF SLUMPING OF THE CHANNEL LINING, UNDERCUTTING OF THE CHANNEL BANKS OR DOWN-CUTTING OF THE CHANNEL.

3. PERMANENT SEEDING AND MULCHING

- A. GRASS SEED SHALL BE FREE FROM NOXIOUS WEED SEEDS AND RECLEANED, GRADE A RECENT CROP SEED, TREATED WITH APPROPRIATE FUNGICIDE AT TIME OF MIXING, DELIVERED TO THE SITE IN SEALED CONTAINERS WITH DEALER'S GUARANTEED ANALYSIS AND EACH VARIETY OF SEED SHALL HAVE PERCENTAGES OF GERMINATION OF NOT LESS THAN 80% AND A PERCENTAGE OF PURITY OF NOT LESS THAN 85%. SOW SEEDS AT A RATE OF 5lbs PER 1,000sq.ft.
- B. WEED SEED CONTENT SHALL NOT EXCEED 0.25% WET, MOLDY OR OTHERWISE DAMAGED SEED WILL BE REJECTED.
- C. SEED MIX PROPORTIONS BY WEIGHT:

Seed Type	% Weight	% Purity	% Germination
Chewing Fescue	35	85	80
Creeping Red Fescue	35	85	80
Perennial Rye	30	85	80

6. PARKING AND DRIVES

- A. PLACE A TEMPORARY STABILIZED CONSTRUCTION EXITS WHERE VEHICLES LEAVE THE SITE AND ENTER EXISTING PAVED ROADS; CONSISTING OF A 6" LAYER OF 1 1/2" TO 3" CRUSHED STONE. TRACKING A SPILLING OF EARTH AND/OR DEBRIS ON PUBLIC STREETS SHALL BE AVOIDED TO THE MAXIMUM EXTENT POSSIBLE. CLEAN UP AND REMOVE SUCH SPILLAGE.
- B. AS THE CRUSHED STONE STABILIZED CONSTRUCTION EXITS CONTINUE TO SCRUB THE SOIL FROM THE TRUCKS, THE STONE LAYER WILL TEND TO FILL WITH SEDIMENTS. WHEN THIS OCCURS, REMOVE THE STONE AND SEDIMENT AND REPLACE IT WITH A CLEAN LAYER OF STONE.
- C. AS SOON AS POSSIBLE AFTER ROADS AND PARKING AREAS ARE CLEARED, GRUBBED AND GRADED TO THE REQUIRED SUBGRADE, THE GRAVEL BASE SHALL BE PLACED.

7. DUST CONTROL

- A. USE TRAFFIC CONTROL TO RESTRICT TRAFFIC TO PREDETERMINED ROUTES. MAINTAIN AS MUCH NATURAL VEGETATION AS IS PRACTICABLE. USE PHASING OF CONSTRUCTION TO REDUCE THE AREA OF LAND DISTURBED AT ANY ONE TIME. THE USE OF TEMPORARY MULCHING, PERMANENT MULCHING, TEMPORARY VEGETATIVE COVER, PERMANENT VEGETATIVE COVER, OR SOODING WILL REDUCE THE NEED FOR DUST CONTROL. USE MECHANICAL SWEEPERS ON PAVED SURFACES WHERE NECESSARY TO PREVENT DUST BUILDUP. STATIONARY SOURCES OF DUST, I.E. ROCK CRUSHERS, SHOULD UTILIZE FINE WATER SPRAYS TO CONTROL DUST.
- B. THE EXPOSED SOIL SURFACE SHOULD BE MOISTENED PERIODICALLY WITH ADEQUATE WATER TO CONTROL DUST.
- C. CALCIUM CHLORIDE SHALL BE EITHER LOOSE DRY GRANULES OR FLAKES FINE ENOUGH TO FEED THROUGH A SPREADER AT A RATE THAT WILL KEEP SURFACE MOIST BUT NOT CAUSE POLLUTION OR PLANT DAMAGE. LIQUID CALCIUM CHLORIDE CAN ALSO BE USED. TO REDUCE POTENTIAL FOR ENVIRONMENTAL DEGRADATION, USE ONLY WHEN OTHER METHODS ARE NOT PRACTICAL.
- D. COVER SURFACE WITH CRUSHED STONE OR COARSE GRAVEL. IN AREAS ADJACENT TO WATERWAYS, USE CHEMICALLY STABLE AGGREGATE.
- E. WHEN TEMPORARY DUST CONTROL MEASURES ARE USED, REPETITIVE TREATMENT SHALL BE APPLIED AS NEEDED TO ACCOMPLISH CONTROL.

9. ADDITIONAL MEASURES

- A. AREAS INSIDE AND OUTSIDE THE CONTRACT WORK LIMITS SHALL BE PROTECTED FROM LUBRICANTS, FUEL, SEDIMENT, LITTER, CONSTRUCTION DEBRIS, CHEMICALS AND OTHER POLLUTANTS.
- B. TAKE PRECAUTIONS AND CONFORM TO ALL FEDERAL, STATE AND LOCAL REGULATIONS TO PREVENT POLLUTANTS FROM BEING DISCHARGED FROM MATERIALS ON SITE, INCLUDING STORAGE PRACTICES TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORMWATER. IMPLEMENT SPILL PREVENTION, CONTAINMENT AND RESPONSE.
- C. DURING CONSTRUCTION, LIQUID PETROLEUM PRODUCTS AND OTHER HAZARDOUS MATERIALS WITH POTENTIAL TO CONTAMINATE GROUNDWATER MAY NOT BE STORED OR HANDLED IN AREAS OF THE SITE DRAINING TO AN INFILTRATION AREA. AN "INFILTRATION AREA" IS ANY AREA OF THE SITE THAT BE DESIGN OR AS A RESULT OF SOILS, TOPOGRAPHY ACCUMULATES RUNOFF THAT INFILTRATES INTO THE SOIL. DUE TO THE SANDY NATIVE SOILS, IMPERVIOUS LINERS OR MATERIALS MUST BE USED TO STORE OR CONTAIN THE HAZARDOUS MATERIALS AND PREVENT THEM FROM ENTERING THE GROUNDWATER.
- D. UNAUTHORIZED NON-STORMWATER DISCHARGES, THE DEPARTMENT OF ENVIRONMENTAL PROTECTION DOES NOT AUTHORIZE DISCHARGES OF THE FOLLOWING:
1. WASTEWATER FROM THE WASHOUT OR CLEANOUT OF CONCRETE, STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS OR OTHER CONSTRUCTION MATERIALS.
 2. FUELS, OILS OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE.
 3. SOAPS, SOLVENTS OR DETERGENTS USED IN VEHICLE AND EQUIPMENT WASHING.
 4. TOXIC OR HAZARDOUS SUBSTANCES FROM A SPILL OR OTHER RELEASE.

10. REMOVAL AND DISPOSAL

WHEN PERMANENT SOIL STABILIZATION HAS BEEN ACHIEVED, TEMPORARY MATERIALS AND DEVICES THAT ARE NOT READILY DEGRADABLE SHALL BE REMOVED AND DISPOSED OF OFF SITE. SILT FENCES, FILTER BERMS AND CATCH BASIN SEDIMENT FILTERS MUST BE FULLY REMOVED. REUSABLE MATERIALS ARE AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR.

12. PLANTING TIME

- A. SEEDING: SEEDING SHALL BE DONE BETWEEN AUGUST 15TH TO SEPTEMBER 15TH AND/OR APRIL 15TH TO JUNE 15TH.
- B. SOODING: SOODING MAY BE DONE BETWEEN APRIL 15TH AND NOVEMBER 15TH.
- C. VARIANCE: IF SPECIAL CONDITIONS EXIST WHICH MAY WARRANT A VARIANCE IN THE ABOVE PLANTING DATES, A WRITTEN REQUEST SHALL BE SUBMITTED TO THE ARCHITECT STATING THE SPECIAL CONDITIONS FOR THE PROPOSED VARIANCE. PERMISSION FOR THE VARIANCE WILL BE GIVEN IF WARRANTED IN THE OPINION OF THE ARCHITECT. REGARDLESS OF THE TIME OF SEEDING, THE CONTRACTOR SHALL BE RESPONSIBLE FOR A FULL GROWTH OF GRASS.
- D. PLACE PERMANENT SOIL STABILIZATION WITHIN 15 DAYS OF FINAL GRADING.

13. INSPECTION AND MAINTENANCE

- A. INSPECT DISTURBED AND IMPERVIOUS AREAS, EROSION CONTROL MEASURES, MATERIALS STORAGE AREAS THAT ARE EXPOSED TO PRECIPITATION AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE AT LEAST ONCE A WEEK AS WELL AS BEFORE AND WITHIN 24 HOURS AFTER A RAIN EVENT AND PRIOR TO COMPLETING PERMANENT STABILIZATION. A PERSON WITH KNOWLEDGE OF EROSION AND STORMWATER CONTROL AND STANDARDS AND CONDITIONS OF THE PERMIT, SHALL CONDUCT THE INSPECTIONS.
- B. UPON DISCOVERY OF A PROBLEM, REPAIR BMPS NO LATER THAN THE END OF THE NEXT WORK DAY. IF ADDITIONAL BMPS OR SIGNIFICANT REPAIRS ARE NECESSARY, IMPLEMENTATION MUST BE COMPLETED WITHIN 7 CALENDAR DAYS AND PRIOR TO A RAIN EVENT.
- C. KEEP A LOG (REPORT) SUMMARIZING THE INSPECTIONS AND CORRECTIVE ACTION TAKEN, INCLUDING THE NAME AND QUALIFICATIONS OF THE PERSON MAKING THE INSPECTIONS, THE DATE OF THE INSPECTIONS AND MAJOR OBSERVATIONS OF OPERATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROLS, MATERIALS STORAGE AREAS AND VEHICLES ACCESS POINTS TO THE PARCEL. MAJOR OBSERVATIONS MUST INCLUDE BMPS THAT NEED MAINTENANCE, BMPS THAT FAILED TO OPERATE AS DESIGNED OR PROVED INADEQUATE FOR A PARTICULAR LOCATION AND LOCATION(S) WHERE ADDITIONAL BMPS ARE NEEDED. NOTE IN THE LOG THE CORRECTIVE ACTION TAKEN AND WHEN IT WAS TAKEN. THE LOG MUST BE MADE ACCESSIBLE TO THE OWNER, ARCHITECT AND REGULATORY AGENCIES' STAFF AND A COPY MUST BE PROVIDED UPON REQUEST. THE PERMITEE SHALL RETAIN A COPY OF THE LOG FOR A PERIOD OF AT LEAST THREE YEARS FROM THE COMPLETION OF PERMANENT STABILIZATION.

<p>1. PROVIDE 4" LOAM, SEED AND MULCH TO DISTURBED AREAS UNLESS OTHERWISE NOTED. PROVIDE EROSION CONTROL MESH ON ALL SLOPES 6:1 OR STEEPER, AND ALONG DITCH CHANNELS.</p> <p>2. GRADE SURFACES TO DRAIN AWAY FROM BUILDING. PUDDLING OF WATER IN PAVED OR UNPAVED AREAS WILL NOT BE ACCEPTABLE EXCEPT FOR AREAS DESIGNATED AS PONDS.</p> <p>3. MAINTAIN TEMPORARY EROSION CONTROL MEASURES FOR THE FULL DURATION OF CONSTRUCTION. INSPECT WEEKLY AND AFTER EACH STORM AND REPAIR AS NEEDED. REMOVE SEDIMENTS FROM THE SITE. PLACE IN AREA OF LOW EROSION POTENTIAL, AND STABILIZE WITH SEED AND MULCH.</p> <p>4. PLACE TEMPORARY SOIL STABILIZATION WITHIN 30 DAYS OF INITIAL DISTURBANCE. PLACE PERMANENT SOIL STABILIZATION WITHIN 7 DAYS OF FINAL GRADING.</p>	<p>1. RELOCATE EXISTING TBM INFORMATION ONTO NEW TBM OF CONTRACTOR'S CHOICE FOR CONSTRUCTION USE PRIOR TO REMOVAL OF EXISTING TBM.</p> <p>2. IF EXISTING ASBESTOS CEMENT PIPE IS ENCOUNTERED, HANDLE AND DISPOSE OF AS ASBESTOS MATERIALS WITH CARE AND IN ACCORDANCE WITH APPLICABLE CODES AND SAFETY STANDARDS.</p> <p>3. EXCAVATE AND STOCKPILE ON-SITE TOPSOIL. TOPSOIL IS TO REMAIN THE PROPERTY OF THE OWNER DURING CONSTRUCTION. AFTER FINAL LOAM AND SEED EXCESS TOPSOIL SHALL BE REMOVED FROM SITE BY CONTRACTOR.</p> <p>4. DIMENSIONS ARE TO FACE OF CURB AND TO FACE OF FOUNDATION UNLESS OTHERWISE INDICATED.</p> <p>5. PAVEMENT EDGES SHALL BE TRUE TO LINE. SAWCUT EXISTING PAVEMENT IN SMOOTH STRAIGHT LINE WHERE NEW PAVEMENT JOINS. PROVIDE TACK COAT LAYER AS SPECIFIED.</p> <p>6. CONTRACTOR SHALL VERIFY SITE CONDITIONS, INCLUDING TEST PITS FOR LOCATIONS AND INVERTS OF UTILITIES, AND REPORT ANY DISCREPANCIES TO ARCHITECT PRIOR TO PROCEEDING WITH THAT PORTION OF THE WORK.</p> <p>7. PROVIDE TRAFFIC CONTROL SIGNAGE AND STRIPING AS SHOWN AND IN ACCORDANCE WITH U.S.D.O.T. MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.</p>	<p>EXISTING</p> <p>PROPOSED</p> <p>BUILDING</p> <p>BIT. CONC. PAVEMENT</p> <p>CURB</p> <p>CHAIN-LINK FENCE</p> <p>GUARDRAIL</p> <p>SIGN</p> <p>BOLLARDS</p> <p>HANDICAP RAMP</p> <p>TREES</p> <p>CONTOUR</p> <p>SPOT ELEVATION</p> <p>GRADE TO DRAIN</p> <p>SOIL BORING, TEST PIT</p> <p>SILT FENCE</p> <p>BARK/STONE CHECK DAM</p> <p>RIP-RAP (SIZE NOTED)</p> <p>CATCH BASIN/DRAIN INLET</p> <p>STEAM MANHOLE</p> <p>STORM DRAIN MANHOLE</p> <p>SEWER MANHOLE</p> <p>TELEPHONE MANHOLE</p> <p>ELECTRIC MANHOLE/PULLBOX</p> <p>WATER VALVE</p> <p>HYDRANT</p> <p>UTILITY POLE</p> <p>LIGHT POLE</p> <p>LIGHT BOLLARD</p> <p>SPOT LIGHT</p> <p>WALL PACK</p> <p>TRANSFORMER PAD</p> <p>POLE TRANSFORMER</p> <p>GEOTHERMAL WELL</p> <p>STORM DRAIN</p> <p>UNDERDRAIN</p> <p>SANITARY SEWER</p> <p>WATER LINE</p> <p>IRRIGATION LINE</p> <p>GAS, PROPANE</p> <p>STEAM LINE</p> <p>GEOTHERMAL WATER</p> <p>UNDERGROUND COMMUNICATION LINE</p> <p>UNDERGROUND ELECTRICAL</p> <p>UNDERGROUND LIGHTING</p> <p>AERIAL ELECTRICAL, TELEPHONE, AND CABLE</p> <p>PROPERTY LINE</p> <p>NOT IN CONTRACT</p> <p>N.I.C.</p>
<p>GRADING NOTES</p> <p>NOT TO SCALE</p>	<p>B3</p> <p>GENERAL SITE NOTES</p> <p>NOT TO SCALE</p>	<p>B2</p> <p>PRIOR TO EXCAVATION, VERIFY THE UNDERGROUND UTILITIES, PIPES, STRUCTURES, AND FACILITIES. PROVIDE THE FOLLOWING MINIMUM MEASURES:</p> <p>A. PRE-MARK THE BOUNDARIES OF YOUR PLANNED EXCAVATION WITH WHITE PAINT, FLAGS OR STAKES, SO UTILITY CREWS KNOW WHERE TO MARK THEIR LINES.</p> <p>B. CALL DIG SAFE, AT EITHER 811 OR 1-888-DIGSAFE, AT LEAST 72 BUSINESS HOURS - BUT NO MORE THAN 30 CALENDAR DAYS - BEFORE STARTING WORK. DON'T ASSUME SOMEONE ELSE WILL MAKE THE CALL.</p> <p>C. IF BLASTING, NOTIFY DIG SAFE AT LEAST 24 BUSINESS HOURS IN ADVANCE.</p> <p>D. WAIT 72 HOURS FOR LINES TO BE LOCATED AND MARKED WITH COLOR-CODED PAINT, FLAGS OR STAKES. NOTE THE COLOR OF THE MARKS AND THE TYPE OF UTILITIES THEY INDICATE. TRANSFER THESE MARKS TO THE AS-BUILT DRAWINGS.</p> <p>E. CONTACT THE LANDOWNER AND OTHER "NON-MEMBER" UTILITIES (WATER, SEWER, GAS, ETC.), FOR THEM TO MARK THE LOCATIONS OF THEIR UNDERGROUND FACILITIES. TRANSFER THESE MARKS TO THE AS-BUILT DRAWINGS.</p> <p>F. RE-NOTIFY DIG SAFE AND THE NON-MEMBER UTILITIES IF THE DIGGING, DRILLING OR BLASTING DOES NOT OCCUR WITHIN 30 CALENDAR DAYS, OR IF THE MARKS ARE LOST DUE TO WEATHER CONDITIONS, SITE WORK ACTIVITY OR ANY OTHER REASON.</p> <p>G. HAND DIG WITHIN 18 INCHES IN ANY DIRECTION OF ANY UNDERGROUND LINE UNTIL THE LINE IS EXPOSED. MECHANICAL METHODS MAY BE USED FOR INITIAL SITE PENETRATION, SUCH AS REMOVAL OF PAVEMENT OR ROCK.</p> <p>H. DIG SAFE REQUIREMENTS ARE IN ADDITION TO TOWN, CITY AND/OR STATE DOT STREET OPENING PERMIT REQUIREMENTS.</p> <p>I. FOR COMPLETE DIG SAFE REQUIREMENTS, VISIT THEIR WEBSITE.</p> <p>J. IF YOU DAMAGE, DISLOCATE OR DISTURB ANY UNDERGROUND UTILITY LINE, IMMEDIATELY NOTIFY THE AFFECTED UTILITY. IF DAMAGE CREATES SAFETY CONCERNS, CALL THE FIRE DEPARTMENT AND TAKE IMMEDIATE STEPS TO SAFEGUARD HEALTH AND PROPERTY.</p> <p>K. ANY TIME AN UNDERGROUND LINE IS DAMAGED OR DISTURBED, OR IF LINES ARE IMPROPERLY MARKED, YOU MUST CALL DIGSAFE.</p>
<p>DIG SAFE NOTES</p> <p>NOT TO SCALE</p>	<p>A2</p> <p>STANDARD SITE LEGEND</p> <p>NOT TO SCALE</p>	<p>A1</p>




AUBURN FORTLAND PORTSMOUTH BOSTON

CENTRAL MAINE COMMUNITY COLLEGE
ECE AREA RENOVATION

AUBURN, MAINE	
Harriman Project No.	16611
Key Plan	

Issues and Revisions
Date Description
03-29-17 CONSTRUCTION DOCUMENTS



PA / PE: FLC	© 2017 Harriman Associates
Drawn By: PLS	

SITE NOTES

C00.2