

2. SECURE TREE AS MAY BE REQUIRED ACCORDING TO TREE SIZE, LOCATION, & WIND/WEATHER CONDITIONS.

3. IF USING ROOTBALL STABILIZATION, FOLLOW MANUFACTURER'S RECOMMENDATIONS.

1. SHRUB TO BE SET PLUMB.

NOTES:

2. SECURE SHRUB AS MAY BE REQUIRED ACCORDING TO SIZE, LOCATION, & WIND/WEATHER CONDITIONS.

-REMOVE ALL METAL OR ROPE BINDINGS & WRAP FROM TOP 1/3 OF ROOT BALL

3. IF USING ROOTBALL STABILIZATION, FOLLOW MANUFACTURER'S RECOMMENDATIONS.

4 PLANTING DETAILS

#### LANDSCAPE SPECIFICATIONS

#### DESCRIPTION

Work under this Section shall include all labor, materials, services, equipment and accessories necessary to furnish and install plant material in complete accordance with these specifications and applicable Drawings.

#### **QUALITY ASSURANCE**

Installer's Personnel Qualifications: Reputable landscape contractor with a min. 5 years experience in landscape construction and licensed to perform work as described in this section.

Comply with all applicable federal, state and local regulations governing landscape materials and work including and especially the City Of Westbrook regulations regarding landscape plantings.

#### WARRANTY

All Plants shall be guaranteed by the landscape contractor for one full year from date of acceptance by the Owner's Representative.

All replacement stock shall be subject to the same warranty requirements as the original stock.

## **MATERIALS**

All plant stock shall be nursery grown and comply with ANSI Z60.1 (American Standard for Nursery Stock).

All stock shall be container grown stock unless otherwise indicated.

Damaged plants and plants that do not meet requirements will be rejected.

Topsoil/Planting Soils: Topsoil or manufactured topsoil shall consist of 3 parts loam amended with 1 part peat humus. Provide friable natural topsoil free of rocks, stones, brush, clay, lumps, twigs, litter, extraneous material, noxious weeds and seeds.

Fertilizer: Slow release packets or tablets containing the following composition: Nitrogen 16%, Phosphoric acid 8%, and Potash 16% (one per shrub at 6-8" depth).

Mulch: Nutri-Mulch from New England Organics (www.earthlifegrows.com) or approved equal.

## INSTALLATION

Modifications of Plan: Any changes to the planting plan or plant list shall be approved by the Landscape Architect.

Site Preparation: The landscape contractor shall notify the Owner's Representative a minimum of 48 hours prior to installation to coordinate installation and location of plant material.

Seasons for planting, unless otherwise directed by the Owner's Representative, shall be within the following dates: Potted and Container Grown Plants: Spring 4/1 to 7/15, and Fall 8/15 to 11/15

Soil Amendments: In locations of high clay content apply gypsum additives to break down the clay.

Planting: All planting shall be done as shown on drawings and as specified herein and in strict accordance with standard horticultural practices.

Pruning: All dead or damaged branches shall be removed from plants. Prune an additional 1/4 of remaining branches to encourage root

Mulch: Each plant shall be individually mulched as indicated in the planting detail on this page.

Clean-up: The Contractor shall remove all debris, construction equipment, excess fill, rocks, and other excess material caused by this work, from the site upon completion of work.

Maintenance: All plants shall be maintained in accordance with standard practices and guaranteed for one year from date of installation.

# 3 PLANTING SPECIFICATIONS

100 Mar. 110 Mar. 1111 Mar	PLANT LIST  Latin Name	Common Name	Size	#	Notes
FC	Forsythia 'Courtesal'	Gold Tide Forsythia	#3	14	
HE	Hemerocallis 'Stella d'Oro'	'Stella d'Oro' Daylilly	#1	40	The month of the control of the cont
НО	Hosta 'Big Daddy'	Big Daddy Hosta	* the control of the	5	titet frag stiller i de etter dekkerer i et i frager frager frager best frager i en die keel en de keel en de e De etter frager frag
MD	Malus 'Donald Wyman'	Donald Wyman Crabapple	1.75"	4	provide trunk protection
PS	Prunus sargentii	Sargent Cherry	1.75"	2	provide trunk protection
<b>TX</b>	Taxus x media 'Tauntonii''	Taunton Yew	15-18"	13	mand of the control o
UA	Ulmus americana 'Princeton'	Princeton Elm	3"	1	provide trunk protection

